

## **Commercial Plat Review**

Date:

City of:

Name:

### **General Comments:**

1. Any relocation of existing facilities or extension of line that has to be built specifically to feed this project will be at full cost to the developer.
2. All property corners and easements must be clearly marked before construction will begin.
3. All off site easements that are needed for Ozarks to extend electrical service to the property must be obtained by developer and easement documentation provided to Ozarks before work begins. On site easements must be shown on plat and recorded with the county.
4. All conduits placed at road crossings by developer must have 48 inch of cover at final grade and marked with post to identify end of conduits. (3 – 6 inch schedule 40 conduits to be used for electric only at all road crossings, conduits must extend past the edge of any obstructions so that they are accessible during construction. Bare minimum of 5 pipes) There must be minimum separation of 12 inches between conduits for electric and conduits for other utilities. This is NESC code 354. All conduits for road crossings and specific widths of U.E. must be shown on final plat before Ozarks Electric will sign the final plat.
5. Transformer must have a minimum of 30 feet clearance from any structure. Any variation of this requirement must have written approval from an Ozarks representative.
6. Developer will need to contact Ozarks Electric and provide them with electrical load information before any cost to developer can be determined.
7. Developer to provide all trench and PVC conduits including PVC sweeps in accordance with Ozarks specifications. No metal conduit or metal sweeps are to be used.
8. Developer must provide Ozarks Electric with a Digital copy (AutoCAD) of the Final plat as well as a hard copy.
9. All Utility Easements to be cleared of all trees, brush, dirt piles, buildings and debris so that the easement is accessible with equipment. If easement is not cleared developer may be subject to extra charges.
10. Developer or contractor must apply for temporary construction service and permanent service before any design and cost is determined by Ozarks.
11. Please contact Ozarks Electric when construction begins on this project and again when construction is within three months of completion.

### **Additional Comments:**